

	Case Name: Residential House Structural Work	Sector	Construction (residential building)
	OR-AS Operations Research - Applications and Solutions www.or-as.be info@or-as.be	Baseline Schedule	Schedule with resources
			Schedule with costs
		Risk Analysis	Random simulation
Submitted by	William & Jef		One of nine std. scenarios
Date	2016		User defined distributions
File Name	C2016-15 Residential House Structural Work	Project Control	Automatic tracking
			Tracking based on user input

1. Project description

Project authenticity

Residential House Structural Work is a project covering the core construction phases of a residential building, including preparation, foundation works, and structural development such as masonry, structural elements, insulation, and facade components. It ensures the building's stability and integrity, forming the essential framework for subsequent finishing works.

2. Project properties

2.1. Baseline Schedule

General		Network topology	
# Activities	13	Serial/Parallel (SP)	66%
Planned Duration (PD)	126d	Activity Distribution (AD)	75%
Budget At Completion (BAC)	95,694.00 €	Length of Arcs (LA)	100%
Renewable Resources	-	Topological Float (TF)	0%
Consumable Resources	-		

* standard eight-hour working days

2.2. Risk Analysis

Random simulation by ProTrack was performed using the default symmetric triangular risk distribution profiles.

	Cost sensitivity		
	avg [%]	std dev [%]	skew [-]
CRI-r	0	0	N/A
CRI-rho	100	0	N/A
CRI-tau	100	0	N/A

	Resource sensitivity		
	avg [%]	std dev [%]	skew [-]
CRI-r	N/A	N/A	N/A
CRI-rho	N/A	N/A	N/A
CRI-tau	N/A	N/A	N/A

	Time sensitivity		
	avg [%]	std dev [%]	skew [-]
CI	69	44	-0.93
SI	80	34	-1.36
SSI	20	21	0.74
CRI-r	23	20	0.83
CRI-rho	22	20	0.83
CRI-tau	17	12	1.16

2.3. Project Control

2.3.1. Simulated forecasting accuracy

The accuracy of time and cost forecasting methods has been evaluated based on Monte Carlo simulation runs using the risk profiles described in section “2.2. Risk Analysis”. Based on these risk profiles, the Mean Absolute Percentage Error (MAPE) and Mean Percentage Error (MPE) has been calculated to evaluate the expected accuracy of the time and cost predictions, EAC(t) and EAC, respectively.

Simulated EAC(t) accuracy		
method - PF	MAPE [%]	MPE [%]
PV - 1	3.43%	0.31%
PV - SPI	7.26%	-2.66%
PV - SCI	7.26%	-2.66%
ED - 1	3.57%	0.56%
ED - SPI	7.19%	-2.73%
ED - SCI	7.19%	-2.73%
ES - 1	6.02%	-5.37%
ES - SPI(t)	35.51%	-34.69%
ES - SCI(t)	35.51%	-34.69%

Simulated EAC accuracy		
method (PF)	MAPE [%]	MPE [%]
1	0.00%	0.00%
CPI	0.00%	0.00%
SPI	3.88%	-3.03%
SPI(t)	28.38%	-28.18%
SCI	3.88%	-3.03%
SCI(t)	28.38%	-28.18%
0.8 CPI + 0.2 SPI	0.46%	-0.18%
0.8 CPI + 0.2 SPI(t)	2.93%	-2.88%

According to the MAPE values¹ the best performance for time forecasting can be expected from the unweighted Earned Schedule method. For cost forecasting the unweighted and CPI-weighted methods should yield the best results.

2.3.2. Tracking description

Tracking authenticity

Manual tracking was performed over 4 tracking periods. The Real Duration and Real Cost mentioned in section “2.3.3. Earned Value Management” are based on manual user input.

The tracking information obtained from the project owner and introduced in ProTrack includes actual activity start dates, durations and costs.

¹ The MAPE gives the best indication for the forecast accuracy (the lower the MAPE, the more accurate the method) since all deviations from the targeted real duration (real cost) are cumulated, whereas for the MPE underestimates can be compensated by overestimates and vice versa, possibly leading to an overly positive evaluation of a certain method. However, the MPE can provide useful information about the nature of the deviations, i.e. does the method rather underestimate or overestimate the real duration (real cost)?

2.3.3. Earned Value Management

2.3.3.1. Performance metrics

	CV [€]	SV [€]	SV(t) [d]	CPI [-]	SPI [-]	SPI(t) [-]	p-factor [-]
avg	-3114.75	-1873.50	-1.25	0.94	0.98	0.99	1.00
std dev	1819.62	3747.00	1.89	0.04	0.04	0.01	0.00
final	-5069.00	0.00	-4.0	0.95	1.00	0.97	1.00

2.3.3.2. Time forecasting

PD	126d	Real Duration	130d	Late/early	3%
----	------	---------------	------	------------	----

EAC(t)	Real Accuracy			
method - PF	avg [d]	std dev [d]	MAPE [%]	MPE [%]
PV - 1	128.50	5.00	3.46%	1.15%
PV - SPI	128.75	5.50	3.65%	0.96%
PV - SCI	137.00	7.16	5.77%	-5.38%
ED - 1	129.50	4.73	2.69%	0.38%
ED - SPI	129.75	5.19	2.88%	0.19%
ED - SCI	133.00	5.35	3.46%	-2.31%
ES - 1	127.25	1.89	2.12%	2.12%
ES - SPI(t)	127.50	1.91	1.92%	1.92%
ES - SCI(t)	130.50	4.51	2.31%	-0.38%

2.3.3.3. Cost forecasting

BAC	95,694.00 €	Real Cost	100,763.00 €	Over/under budget	5%
-----	-------------	-----------	--------------	-------------------	----

EAC	Real Accuracy			
method (PF)	avg [€]	std dev [€]	MAPE [%]	MPE [%]
1	98808.75	1819.62	1.94%	1.94%
CPI	101399.11	4164.91	2.59%	-0.63%
SPI	98972.55	1964.38	1.78%	1.78%
SPI(t)	98825.33	1832.13	1.92%	1.92%
SCI	101570.59	4111.63	2.47%	-0.80%
SCI(t)	101416.47	4158.26	2.57%	-0.65%
0.8 CPI + 0.2 SPI	100868.92	3275.25	2.10%	-0.11%
0.8 CPI + 0.2 SPI(t)	100839.46	3283.38	2.13%	-0.08%