

	Case Name: C2018-11	Sector	Construction	
	OR-AS Operations Research - Applications and Solutions www.or-as.be info@or-as.be	Baseline schedule	Schedule with resources	
			Schedule with costs	
		Risk analysis	Random Simulation	
Submitted by	Mayté & Thymo		One of nine std. scenarios	
Date	2018		User defined distributions	
File Name	C2018-11	Project Control	Automatic tracking	
			Tracking based on user input	

1. Project description

Project Authenticity

The project consists of *activity* data that were obtained directly from the actual project owner.

2. Project properties

2.1. Baseline schedule

General	
# Activities	36
Planned Duration (PD)	9 days*
Budget at Completion (BAC)	-
Renewable Resources	-
Consumable Resources	-

Network Topology	
Serial/Parallel (SP)	42%
Activity Distribution (AD)	39%
Length of Arcs (LA)	0%
Topological Float (TF)	58%

* Standard eight-hour working days

2.2. Risk analysis

Random simulation by ProTrack was performed using the default symmetric triangular risk distribution profiles.

	Cost sensitivity		
	avg (%)	std dev (%)	skew (-)
CRI-r	N/A	N/A	N/A
CRI-rho	N/A	N/A	N/A
CRI-thau	N/A	N/A	N/A

	Time sensitivity		
	avg (%)	std dev (%)	skew (-)
CI	61,1	48,7	-0,5
SI	47,0	45,6	0,3
SSI	7,2	16,8	2,2
CRI-r	8,9	15,4	2,2
CRI-rho	38,7	18,1	-0,9
CRI-thau	67,9	38,9	-0,5

	Resource sensitivity		
	avg (%)	std dev (%)	skew (-)
CRI-r	N/A	N/A	N/A
CRI-rho	N/A	N/A	N/A
CRI-thau	N/A	N/A	N/A