

	Case Name: BAM deelproject 3a	Sector	Construction	
	OR-AS Operations Research - Applications and Solutions www.or-as.be info@or-as.be	Baseline schedule	Schedule with resources	
			Schedule with costs	
		Risk analysis	Random Simulation	
Submitted by	Mayté & Thymo		One of nine std. scenarios	
Date	2019		User defined distributions	
File Name	C2019-24 BAM deelproject 3a	Project Control	Automatic tracking	
			Tracking based on user input	

1. Project description

Project Authenticity

The project consists of *activity* data that were obtained directly from the actual project owner.

2. Project properties

2.1. Baseline schedule

General	
# Activities	1373
Planned Duration (PD)	1041 days*
Budget at Completion (BAC)	-
Renewable Resources	-
Consumable Resources	-

Network Topology	
Serial/Parallel (SP)	1%
Activity Distribution (AD)	61%
Length of Arcs (LA)	0%
Topological Float (TF)	78%

* Standard eight-hour working days

2.2. Risk analysis

Random simulation by ProTrack was performed using the default symmetric triangular risk distribution profiles.

	Cost sensitivity		
	avg (%)	std dev (%)	skew (-)
CRI-r	N/A	N/A	N/A
CRI-rho	N/A	N/A	N/A
CRI-thau	N/A	N/A	N/A

	Time sensitivity		
	avg (%)	std dev (%)	skew (-)
CI	0,8	8,6	11,0
SI	3,5	10,2	7,2
SSI	0,1	2,4	22,3
CRI-r	6,5	7,1	2,2
CRI-rho	19,2	18,7	0,9
CRI-thau	36,9	38,2	0,9

	Resource sensitivity		
	avg (%)	std dev (%)	skew (-)
CRI-r	N/A	N/A	N/A
CRI-rho	N/A	N/A	N/A
CRI-thau	N/A	N/A	N/A